

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs. a. p.
14	Providing Hollow Gopuram for the Temple, 12' high with a dome at top, complete with ornamental plaster moulding and stucco work, etc., mould solid	C.ft.	1 0 0	871	
15	Providing Brass finials, gold gilt, etc., as per approved design	L.S.	..	..	
16	Flooring with granite stone, 18" square laid diagonally over 3" lime concrete and pointed and one line dressed	Sqr.	45 0 0	5.02	
17	Ornamental Arch way over parapet level in front	L.S.	..	..	

N. KRISHNIENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 24th June 1936.

The attention of the public is invited to the notification, published in pages 974-976 of the issue of the *Mysore Gazette*, dated 2nd July 1936, inviting tenders for the work of restoration of breached Kolimpalli Sunnapralakere, Register No. 795, Minor, Bagepalli Taluk.

The last date fixed for the receipt of tenders in this Office is 2 P.M. on 27th July 1936.

N. SUBBA RAO,
Executive Engineer.

Notification dated 7th July 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 6th August 1936, for restoring Dinneri Kanagalkere Minor tank, Register No. 276 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Dinneri Kanagalkere Minor Tank, Register No. 276 of Malur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry, regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 800 has to be shown every month.

Abstract estimate for restoring Dinneri Kanagalkere, Register No. 276 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	<i>I. Bund at R. L. 55.50 top width 4½' slopes 1½ to 1 and 2:1.</i>				
1	Jungle clearing with removal of roots, etc., complete	Grades	3 0 0	18	
2	Removing ant-hills and refilling them with sand and gravel	Each	0 8 0	10	
3	Cutting trench for the grips of new earth	Grades	2 0 0	16	
4	Earth work to bund with watering and consolidating	C.yd.	0 3 0	4,511	
5	Turfing to slopes	S.yd.	0 0 9	3,764	
6	Removing and resetting old stone revetment with new jelly backing and wedging	C.yd.	0 0 8	287	
7	New stone revetment	C.yd.	1 8 0	1,398	
8	Providing and fixing painting, etc., complete	Each	1 12 0	18	
9	Do Index stones	"	0 6 0	18	
10	Do B. M. stones	"	2 8 0	2	
11	Do Register No. and Date Stone	"	3 0 0	1	
12	Do gauge stones	"	15 0 0	1	
	Total amount for bund		..	..	
	<i>II. Constructing a Waste-Weir at R. L. 51.00 140 feet long.</i>				
1	Earthwork excavating foundations and filling	C.yds.	0 3 0	161	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 3	1,012	
3	Burnt brick in surki mortar	"	0 4 6	3,610	
4	Burnt stone slabs 6" thick and dressed and fixed, complete	S.ft.	0 5 0	604	
5	New stone work for apron	C.yd.	1 12 0	204	
5a	Providing concrete rib at the junction of body wall and apron	L. S.	..	..	
6	Plastering with surki mortar	Sqr.	4 0 0	34.69	
7	Jelly filling in below apron	C.yd.	1 0 0	230	
8	Providing Joggle joints	Each	0 8 0	18	
9	Providing clay ramp in front of body wall	C.yd..	0 4 0	114	
	Total for the weir		..	..	
	<i>Constructing a Rough Stone Drop 45 feet long at R. L. 44.00.</i>				
1	Earthwork excavating foundations	C.yd.	0 3 0	22	
2	New stone work for apron and body wall	"	1 12 0	177	
	Total for drop		..	..	
	<i>III. Constructing a New Masonry Cast Iron Pipe Sluice of 8" dia. at R. L. 42.00.</i>				
1	Dismantling old sluice	L. S.	..	..	
2	Cut opening the bund and filling in the same watering and consolidating	C.yd.	0 5 6	62	
3	Earthwork excavating foundations	"	0 3 0	9	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
4	Stone jelly concrete in surki mortar	C.ft.	0 4 3	211	
5	Burnt brick in surki mortar	"	0 4 6	345	
6	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 5 0	68	
7	Plastering with surki mortar	"	4 0 0	4.52	
8	Cutting holes in the orifice slabs		L. S.		
9	Supplying 8" dia. cast iron pipes including carting, fixing, and jointing, etc., complete ..	R.ft.	4 0 0	36	
10	Providing and fixing teakwood plug and iron rod with locking arrangements, etc., complete		L. S.		
	Total for the sluice ..		..	..	

Notification dated 7th July 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 27th July 1936, for restoring Attur tank, Register No. 1—561, Minor tank, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Attur tank, Register No. 1—561, Minor tank, Chintamani Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 700 has to be shown every month.

Abstract estimate for restoring Attur Tank Register No. 1—561 in Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	<i>1 Bund at R. L. 57.00 top width 4½'</i> <i>Slopes 2:1 and 1½:1.</i>				
1	Earthwork with consolidation	C.yds.	0 4 9	5,829	
2	Cutting trenches on slopes of bund	Each	2 0 0	16	
3	Removing the silt in breach		L. S.	..	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
3a	Puddle wall at breach	C.yds.	0 9 0	164	
4	Turfing	S.yd.	0 0 9	4,767	
5	Cutting tail of bund	C.yds.	0 3 0	133	
6	Removing and resetting old stone work ..	"	0 8 0	50	
7	New stone work (revetment)	"	1 8 0	677	
7a	Gravel backing to revetment	"	0 8 0	307	
8	Grade stone including cutting figures, painting, etc., complete	No.	1 12 0	17	
9	Do Index stones	"	0 6 0	17	
10	Register No. and date stones	"	3 0 0	1	
11	B. M. stones do	"	2 8 0	2	
12	Providing training bank for weir draft channel to prevent surplus water damaging rear of bund at the breached portion including revetting the slopes	L. S.	..		
	Total for Bund ..				
	<i>II. Constructing a cast iron pipe sluice at R. L. 47'00.</i>				
1	Earthwork cut opening the bund and consolidating after the construction	C.yd.	0 5 0	67	
2	Earthwork excavation for foundation	"	0 3 0	7	
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	165	
4	Burnt size stone in surki mortar	"	0 5 0	350	
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 5 0	77	
6	Pointing with cement mortar	Sqr.	4 0 0	4.11	
7	Drilling holes in slabs	L. S.	..		
8	Providing teakwood plug and rod including locking arrangement	L. S.	..		
9	Supplying and fixing cast iron pipes of 9" dia. including Railway fair, Cart hire, etc., complete	R.ft.	4 0 0	24	
	Total for Sluice ..		..	..	
	<i>III. Constructing a masonry waste weir 230 feet long at R. L. 52'00.</i>				
1	Earthwork excavation	C.yd.	0 3 0	183	
2	Concrete in surki mortar	C.ft.	0 4 3	481	
3	Burnt brick in surki mortar	"	0 4 6	730	
4	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 5 0	923	
5	Plastering with surki mortar	Sqr.	4 0 0	12.00	
6	Joggle joints	Each	0 12 0	30	
7	New stone work for apron with jelly filling ..	C.yds.	1 12 0	180	
8	Draft clearing	L. S.	..	..	
	Total for Weir ..		..	..	

P. RAJAGOPALAN,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 29th June 1936.

The attention of the public is invited to the notification, dated 2nd July 1936 of the *Mysore Gazette* under Part IV, Pages 976-977, calling for tenders for deviation of Nanjangud-Hassanur ghat road in Chamarajnagar Town, through Parivarakere. The last date of receipt of tender is 20th July 1936.